PLANT SCHEDULE

SYMBOL	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE				
DECIDUOUS TREES									
	со	1	Celtis occidentalis 'JFS-KSU1'	Prairie Sentinel® Hackberry	3" CAL.	3			
	LSS	3	Liquidambar styraciflua 'Slender Silhouette'	Slender Silhouette Sweetgum	3" CAL.				
	NST	1	Nyssa sylvatica 'Tupelo Tower'	Tupelo Tower Black Gum	3" CAL.				
	QP	1	Quercus palustris 'Pringreen'	Green Pillar® Pin Oak	3" CAL.				
CVMAPOL	CODE	OTV	DOTANICAL NAME	COMMON NAME	CIZE	CDACINIC			
SYMBOL	CODE	<u>QTY</u>	BOTANICAL NAME	COMMON NAME	SIZE	SPACING			
<u>SHRUBS</u>									
(z •)	IH	6	llex crenata 'Helleri'	Heler Japanese Holly	18 - 24" HT.	36" o.c.			
\bigoplus	IGS	25	llex glabra `Shamrock`	Shamrock Inkberry	18 - 24" HT.	36" o.c.			
PERENNIALS									
	HRR	127	Hemerocallis x `Rosy Returns`	Rosy Returns Daylily	#1 POT	18" o.c.			
PLANTERS									
Erring State of the state of th	NF-R	6	Nepeta x faassenii	Catmint	#1 POT	18" o.c.			
	PAH-R	7	Pennisetum alopecuroides 'Hameln'	Dwarf Fountain Grass	#1 POT	18" o.c.			
\ \ \ \	SRA-R	8	Sedum rupestre 'Angelina'	Angelina Stonecrop	#1 POT	18" o.c.			
	SA-R	6	Sedum x 'Autumn Joy'	Autumn Joy Sedum	#1 POT	18" o.c.			
ORNAMENTAL GRASSES									
	CKF	147	Calamagrostis x acutiflora `Karl Foerster`	Karl Foerster Feather Reed Grass	#1 POT	18" o.c.			
* * * * * * * * * * * * * * * * * * *	ES	37	Eragrostis spectabilis	Purple Lovegrass	#1 POT	18" o.c.			
+ + + + + + + + + + + + + + + + + + + +	PVS	26	Panicum virgatum `Shenandoah`	Shenendoah Switch Grass	#2 POT	30" o.c.			


Plant Note

1. ALL TREE AND STUMP REMOVAL SHALL BE IN ACCORDANCE WITH THE ASIAN LONGHORNED BEETLE PROGRAM REQUIREMENTS. ALL NEW TREES AND SHRUB PLANTINGS SHALL BE ASIAN LONGHORNED BEETLE AND EMERALD ASH BORER RESISTANT.

Planting Notes

- 1. ALL PROPOSED PLANTING LOCATIONS SHALL BE STAKED AS SHOWN ON THE PLANS FOR FIELD REVIEW AND APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 2. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL BELOW GRADE AND ABOVE GROUND UTILITIES AND NOTIFY OWNERS REPRESENTATIVE OF CONFLICTS.
- NO PLANT MATERIALS SHALL BE INSTALLED UNTIL ALL GRADING AND CONSTRUCTION HAS BEEN COMPLETED IN THE IMMEDIATE AREA. CONTRACTOR SHALL NOTIFY OWNER'S REPRESENTATIVE OF ANY
- 4. A 3-INCH DEEP MULCH PER SPECIFICATION SHALL BE INSTALLED UNDER ALL TREES AND SHRUBS, AND IN ALL PLANTING BEDS, UNLESS OTHERWISE INDICATED ON THE PLANS, OR AS DIRECTED BY OWNER'S REPRESENTATIVE.
- 5. ALL TREES SHALL BE BALLED AND BURLAPPED, UNLESS OTHERWISE NOTED IN THE DRAWINGS OR SPECIFICATION, OR APPROVED BY THE OWNER'S REPRESENTATIVE.
- 6. FINAL QUANTITY FOR EACH PLANT TYPE SHALL BE AS GRAPHICALLY SHOWN ON THE PLAN. THIS NUMBER SHALL TAKE PRECEDENCE IN CASE OF ANY DISCREPANCY BETWEEN QUANTITIES SHOWN ON THE PLANT LIST AND ON THE PLAN. THE CONTRACTOR SHALL REPORT ANY DISCREPANCIES BETWEEN THE NUMBER OF PLANTS SHOWN ON THE PLANT LIST AND PLANT LABELS PRIOR TO BIDDING.
- 7. ANY PROPOSED PLANT SUBSTITUTIONS MUST BE REVIEWED BY LANDSCAPE ARCHITECT AND APPROVED IN WRITING BY THE OWNER'S REPRESENTATIVE.
- 8. ALL PLANT MATERIALS INSTALLED SHALL MEET THE SPECIFICATIONS OF THE "AMERICAN STANDARDS FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN AND CONTRACT DOCUMENTS.
- 9. ALL PLANT MATERIALS SHALL BE GUARANTEED FOR ONE YEAR FOLLOWING DATE OF FINAL ACCEPTANCE.
- 10. AREAS DESIGNATED "LOAM & SEED" SHALL RECEIVE MINIMUM 6" OF LOAM AND SPECIFIED SEED MIX. LAWNS OVER 2:1 SLOPE SHALL BE PROTECTED WITH EROSION CONTROL FABRIC.
- 11. ALL DISTURBED AREAS NOT OTHERWISE NOTED ON CONTRACT DOCUMENTS SHALL BE LOAM AND SEEDED OR MULCHED AS DIRECTED BY OWNER'S REPRESENTATIVE.
- 12. THIS PLAN IS INTENDED FOR PLANTING PURPOSES. REFER TO SITE / CIVIL DRAWINGS FOR ALL OTHER SITE CONSTRUCTION INFORMATION.


- 1. CONTRACTOR SHALL PROVIDE COMPLETE IRRIGATION SYSTEM DESIGN AND INSTALLATION FOR PLANTINGS AND LAWN AREAS. DESIGN SHALL BE CERTIFIED BY A PROFESSIONAL LANDSCAPE ARCHITECT, ENGINEER, OR CERTIFIED IRRIGATION DESIGNER. DESIGN PLANS SHALL BE SUBMITTED TO OWNER'S REPRESENTATIVE FOR APPROVAL.
- 2. CONTRACTOR SHALL PROVIDE ALL MATERIALS, LABOR, AND EQUIPMENT FOR THE COMPLETE INSTALLATION OF THE IRRIGATION SYSTEM.
- 3. CONTRACTOR SHALL PROVIDE DRAWINGS, MATERIAL SPECIFICATIONS, SCHEMATICS, AND OTHER LITERATURE AS MAY BE REQUIRED, FOR ALL CONDUIT, CONTROLS, TIMERS, VALVES, SPRINKLER HEADS, CONNECTORS, WIRING, RAIN GAUGE, ETC. TO THE OWNER'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO INSTALLATION.
- 4. CONTRACTOR SHALL COORDINATE HIS WORK WITH THE GENERAL CONTRACTOR AND SUB CONTRACTORS.
- 5. BACKFLOW PREVENTER AND METER IS REQUIRED. IT SHALL BE IN CONFORMANCE WITH STATE AND MUNICIPAL REQUIREMENTS.
- 6. IRRIGATION CONTROL PANEL, BACKFLOW PREVENTER AND METER SHALL BE LOCATED IN THE BUILDING MECHANICAL ROOM. COORDINATE WITH THE GENERAL CONTRACTOR.
- 7. SITE CONTRACTOR SHALL PROVIDE 4" SCHEDULE 40 PVC SLEEVES UNDER PAVEMENT TO PROVIDE ACCESS FOR IRRIGATION LINES TO ALL IRRIGATED AREAS.



4th Floor Roof Deck Planting Plan

Planter Notes


- 1. PLANTERS WILL BE SPECIFIED BY OTHERS.
- 2. ASSUMED THAT PLANTERS WILL BE HAND WATERED, WITH A SOIL DEPTH OF AT LEAST 18", AND THAT THE PLANTERS WILL BE FREE DRAINING.
- 3. PLANTER SOIL SHALL BE A STANDARD POTTING SOIL MIXTURE.



1. LOOSEN ROOTS AT THE OUTER EDGE

OF ROOTBALL OF CONTAINER GROWN SHRUBS.

Shrub Bed Planting Source: VHB LD_601



Tree Planting (For Trees Under 4" Caliper)

42 IN. O.C.

48 IN. O.C.

54 IN. O.C.

6 IN. O.C.

8 IN. O.C. 10 IN. O.C.

12 IN. O.C.

15 IN. O.C.

18 IN. O.C.


24 IN. O.C.

30 IN. O.C.

48 IN. O.C. 54 IN. O.C.

60 IN. O.C.

PLANT SPACING PLANT SPACING("A") ROW SPACING ("B") 5 IN. O.C. 7 IN. O.C. 8 ½ IN. O.C. 10 ½ IN. O.C. 13 IN. O.C. 16 IN. O.C. 21 IN. O.C. 26 IN. O.C. 30 IN. O.C.



Perennial and Ornamental Grass Planting

9/21 LD_602



Suite 500 Worcester, MA 01608 508.752.1001

10 Grosvenor Street Worcester, MA

LD_602

No.	Revision	Date	Appvd
1	Address City Comments	08/30/2024	BMG
2	Roof Deck Plantings	09/30/2024	BMG
3	Address City Comments	10/21/2024	BMG

Designed by	Checked by		
SC	MK		
Issued for	Date		
Local Approvals	July 11, 2024		





16406.00