

HISTORIC LEVEL 3 ALTERATION: 114 AUSTIN STREET

PROJECT LOCATION
114 AUSTIN STREET
WORCESTER, MA 01609

CLIENT
POLAR VIEWS
89 WEST MAIN STREET, UNIT 101
NORTHBOROUGH, MA 01532
MR DANIEL YARNIE

CIVIL ENGINEER
J.M. GRENIER ASSOCIATES, INC.
118 TURNPIKE ROAD, SUITE 200
SOUTHBOROUGH, MA 01772
MR. JOHN GRENIER
JMGRENIER@TOWNISP.COM
(T) 508.845.2500

ARCHITECT
DIXON SALO ARCHITECTS, INC.
300 MAIN STREET, FIRST FLOOR
WORCESTER, MA 01608
MR. JESSE HILGENBERG
JHILGENBERG@DIXONSALOARCHITECTS.COM
(T) 508.755.0533

LIST OF DRAWINGS

T-1.0	TITLE SHEET
T-1.1	GENERAL NOTES & DETAILS
ARCHITECTURAL	
A-0.1	CONCEPTUAL FOUNDATION PLAN
A-1.1	BASE PLAN
A-1.2	FIRST FLOOR PLAN
A-1.3	SECOND FLOOR PLAN
A-1.4	ROOF PLAN
A-2.0	SIDE ELEVATION
A-2.1	QUINCY STREET ELEVATION
A-2.2	AUSTIN STREET ELEVATION
A-2.3	REAR ELEVATION
A-2.4	PROPOSED MATERIAL PHOTOS
A-2.5	CARRIAGE HOUSE SECTION
A-2.6	NEW BUILDING SECTION
A-4.0	KITCHEN AND BATHROOM INTERIOR ELEVATIONS
A-8.0	DOOR & WINDOW TYPES, FINISH SCHEDULE

NOTE:
PORTIONS OF THE PROJECT ARE TO BE DESIGN-BUILD UNDER THE GENERAL CONTRACTOR. GENERAL CONTRACTOR TO PROVIDE ARCHITECT WITH STRUCTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION, FIRE ALARM AND PLUMBING DRAWINGS FOR REVIEW BEFORE SUBMISSION FOR PERMIT.



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

ABBREVIATIONS

ACOUSTICAL CEILING TILE	A.C.T	MANUFACTURED	MFD
ACOUSTIC	ACST	MARBLE	MAR
ABOVE FINISHED FLOOR	AF	MASONRY	MAS
ALUMINUM	ALUM	MASONRY OPENING	MSRY
ARCHITECT	ARCH	MATERIAL	MAT
AVERAGE	AVG	MASONRY	MXX
BEAM	BM	MECHANICAL	MAX
BOARD	BD	METAL	ML
BRASS	BR	METER	M
BRONZE	BRZ	MIRRMUM	MIR
BUILDING	BLDG	MISCELLANEOUS	MISC
BULLET IN	BLIN	MULLION	MULL
CABINET	CAB	NATURAL	NAT
CEILING	CLG	NOMINAL	NOM
CENTER LINE	CL	NOT IN CONTRACT	NIC
CENTIMETER	CM	NOT TO SCALE	NIS
CERAMIC	CER	NUMBER	N
CLEAR	CLR	ON CENTER	OC
COLD WATER	CW	OPENING	OPG
COLUMN	COL	OPPOSITE	OPP
CONCRETE	CONC	PAINTED	PID
CONCRETE MASONRY UNIT	CMU	PARTITION	PN
CONSTRUCTION	CONST	PLASTER	PL
CONTINUOUS	CONTR	PLASTIC LAMINATE	PLAM
CONTRACTOR	CONTR	FLUORING	FLG
DEMOLITION	DEMO	PLYWOOD	PLYWD
DETAIL	DET	PRESSURE TREATED	P.T.
DIAMETER	DIA OR	QUANTITY	QTY
DIMENSION	DM	QUARRY TILE	QT
DOOR	DR	RADIUS	R
DOWN	DN	REFERENCE	REF
DRAWING	DWG	REINFORCE	RENF
DRAINING FOUNTAIN	DF	REMOVE	RMV
EACH	EA	REQUIRED	REQD
ELECTRIC	ELEC	REVISION	REV
ELECTRIC WATER COOLER	EW	RIBB	RS
EQUAL	EQ	ROOM	RM
EQUIPMENT	EQUIP	ROUGH OPENING	RO
ESTIMATE	EST	SCHEDULE	SCH
EXISTING	EXIST	SECTION	SECT
EXTERIOR	EXT	SHEET	SH
FABRICATE	FAB	SIMILAR	SIM
FEET	OR FT	SOLID CORE	SC
FINISH	FIN	SPECIFICATIONS	SPEC
FINISHED ALL OVER	FAO	SQUARE FEET	SF
FIREPROOF	FP	SQUARE INCHES	SQ IN.
FLOOR	FLR	STAINLESS STEEL	SS
FLORESCENT	FLUOR	STANDARD	STD
FULL SIZE	FS	STEEL	ST
FURNISH	FURN	STRUCTURAL	STR
GAUGE	GA	SUSPENDED	SUSP
GENERAL	GEN	SYSTEM	SYS
GLASS	GL	TEMPERATURE	TEMP
GYP BOARD	GYP BD	TONGUE & GROOVE	T&G
HARDWARE	HW	TREAD	TR
HARDWOOD	HWWD	TYPICAL	TYP
HEIGHT	HT	UNFINISHED	UNF
HOLLOW CORE	HC	URNAL	UR
HORIZONTAL	HOR	VENT THROUGH ROOF	VTR
HOT WATER	HW	VERIFY IN THE FIELD	VIF
INSULATION	INS	VERTICAL	VERT
INTERIOR	INT	VINTL TILE	VINTL
JUNCTION BOX	JBOX	WAINSCOT	WCS
LAVATORY	LAV	WATER CLOSET	WC
LIGHT	LIC	WATERPROOF	WP
LIGHTING	LICHT	WEIGHT	WF
LINEAR	LN	WIDTH	W
LINOLEUM	LNO	WITH	W
MANUFACTURER	MFR	WITHOUT	WO
GANVAZE	GANV	WOOD	WD
GYP BOARD	GWB	WROUGHT IRON	WI
		YARD	YD

LEGEND

SYMBOLS	MATERIALS	DRAWING SYMBOLS
	EARTH - LOAM	EXIST WALL TO REMAIN
	EARTH - FILL	DEMO EXIST WALL
	GRAVEL	NEW CONSTRUCTION
	SAND	PULL STATION
	CONCRETE	EMERGENCY EXIT SIGN
	CONCRETE MASONRY	HORN/STROBE
	BRICK	STROBE
	BITUMINOUS CONCRETE	EMERGENCY BATTERY UNIT
	BATT INSULATION	REMOTE HEAD
	RIGID INSULATION	EMERGENCY EXIT SIGN W/BATTERY UNIT
	WOOD - FRAMING	FIRE EXTINGUISHER
	WOOD - FINISH	CARD READER ACCESS
	PLYWOOD - SMALL SCALE	EMERGENCY SHOWER
	ACOUSTICAL TILE	THERMOSTAT
	STEEL	PHOTOELECTRIC SMOKE & CO DETECTOR
	ALUMINUM	HEAT & CO DETECTOR
		FLOURESCENT LIGHTING FIXTURE
		SPRINKLER HEAD
		HVAC GRILLE - RETURN
		HVAC - SUPPLY
		RECESSED DOWN LIGHT
		MOTION DETECTOR

LOCUS MAP



	SCHEMATIC	07.20.2023
	DESIGN DEVELOPMENT	10.25.2023
	BID	N/A
	PERMIT	07.09.2024
	CONSTRUCTION	
	EXISTING CONDITIONS	

4	
3	
2	
1	

DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
114 AUSTIN ST
WORCESTER, MA 01609

SHEET TITLE:
TITLE SHEET

SHEET NUMBER:
T-1.0

GENERAL DEMOLITION NOTES

A. CONTRACTOR SHALL VISUALLY INSPECT THE SITE TO DETERMINE THE CONDITION OF EXISTING CONSTRUCTION AND FAMILIARIZE HIMSELF/HERSELF WITH THE PROPOSED WORK.

- ALL WORK SHALL COMPLY WITH MUNICIPAL, STATE AND FEDERAL RULES AND REGULATIONS, LAWS AND ORDINANCES OF ALL THE AUTHORITIES HAVING JURISDICTION.
- DISCONNECTION OF UTILITIES REQUIRED BY THE WORK SHALL BE PERFORMED BY QUALIFIED PERSONNEL.
- ALL WORK IS TO COMPLY WITH APPLICABLE PROVISIONS OF ANSI CODE FOR BUILDING CONSTRUCTION: ANS110.6, SAFETY OF DEMOLITION.
- UTILITY LINES TO BE ABANDONED SHALL BE DISCONNECTED, REMOVE AS REQUIRED, AND/OR CAPPED OFF IN ACCORDANCE WITH APPLICABLE CODE AND REGULATIONS.
- REMOVE ALL AREAS SHOWN DASHED [TYPICAL] ON DEMOLITION PLANS.
- CONTRACTOR TO PROTECT ALL EXISTING AREAS BEYOND LIMIT OF WORK OR ITEMS THAT ARE TO REMAIN, AS REQUIRED.
- COORDINATE DEMOLITION WORK WITH PROPOSED NEW WORK SHOWN ON PROJECT DRAWINGS.
- THE GENERAL CONTRACTOR SHALL NOT INTERFERE WITH NORMAL ACTIVITY IN OR ADJACENT TO THE BUILDING, AND IS SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PREVENT EXCESSIVE DUST, AND NOISE. ACCESS AND EGRESS TO AND FROM THE EXISTING BUILDING AS WELL AS FIRE PROTECTION IS TO BE MAINTAINED AT ALL TIMES THROUGHOUT THE ENTIRE CONSTRUCTION PROCESS.
- PROVIDE ALL TEMPORARY SHORING BRACING, FRAMING, AND PROTECTION OF EXISTING WORK TO REMAIN BEFORE PROCEEDING WITH DEMOLITION AND DURING ALTERATION WORK.
- PERFORM DEMOLITION WORK AS REQUIRED TO ACCOMMODATE NEW CONSTRUCTION. CONTRACTOR SHALL VERIFY THAT ALL REMOVED COMPONENTS ARE NOT STRUCTURAL. NOTIFY ARCHITECT BEFORE REMOVING ANY STRUCTURAL MEMBERS. NOTIFY ARCHITECT IN CASE OF DISCREPANCY BEFORE PROCEEDING WITH WORK.
- IF DURING DEMOLITION CONDITIONS ARE REVEALED THAT MAY JEOPARDIZE THE INTEGRITY OF THE STRUCTURE OR PRECLUDE THE DESIGN INTENT, THE GENERAL CONTRACTOR SHALL NOTIFY THE ARCHITECT IMMEDIATELY.
- DEMOLITION PLANS ASSUME THAT PORTIONS OF EXISTING WIRING, PLUMBING, EQUIPMENT, DUCTWORK, ETC., IN AREAS OF NEW WORK WILL BE REQUIRED TO BE REMOVED/RELOCATED TO MEET THE REQUIRED DESIGN PARAMETERS OF THE NEW WORK. PRIOR TO COMMENCING DEMOLITION/RELOCATION, CONTRACTOR SHALL VERIFY SPECIFIC CONDITIONS IN THE FIELD AND COORDINATE WITH GC AND ARCHITECT. (SEE M.E.P. DEMOLITION NOTES).
- BEFORE DISPOSING OF ANY REMOVED ITEMS, CONSULT WITH OWNER AND VERIFY POSSIBLE RE-USE, SALVAGE, OR DISPOSAL OF ANY EXISTING ITEMS AND EQUIPMENT, INCLUDING BUT NOT LIMITED TO, PLUMBING, FIXTURES, EQUIPMENT, LIGHT FIXTURES AND DOORS, ETC.

B. CUTTING AND PATCHING

- GENERAL CONTRACTOR IS RESPONSIBLE FOR COORDINATION OF ALL SUBCONTRACTORS, DEMOLITION CUTTING AND PATCHING
- ALL PARTITIONS, FLOORS, CEILINGS OR ITEMS TO BE REMOVED SHALL BE CLEANLY CUT BACK TO THE LIMITS SHOWN ON THE PLANS, SECTIONS, AND DETAILS OR AS DIRECTED BY THE ARCHITECT.
- ALL EXISTING FLOORS, WALLS, AND CEILINGS AFFECTED BY NEW WALL LOCATIONS ARE TO BE PATCHED AND REPAIRED AS NECESSARY TO PROVIDE A SMOOTH UN-NOTICEABLE TRANSITION OF NEW AND EXISTING MATERIALS AND SURFACES.
- PROVIDE CUTTING AND PATCHING AS REQUIRED FOR ALL DEMOLITION AND ALTERATION WORK. CUTTING AND PATCHING INCLUDE CUTTING INTO OR THROUGH TO PROVIDE FOR THE INSTALLATION OR PERFORMANCE OF OTHER WORK, AND THE SUBSEQUENT FITTING AND PATCHING REQUIRED TO RESTORE THE CUT SURFACES TO THEIR ORIGINAL CONDITION.
- REMOVE EXISTING INTERIOR FINISHES AND MATERIALS AS REQUIRED TO ACCOMMODATE NEW WORK. ALL ITEMS ARE TO BE REMOVED IN A MANNER SO AS TO NOT DAMAGE THE EXISTING MATERIALS OR FINISHES THAT ARE TO REMAIN OR BE REINSTALLED.
- PERFORM DEMOLITION WORK CAREFULLY. REMOVE MASONRY, STEEL, CONCRETE, WALLS AND OTHER STRUCTURAL ELEMENTS IN SMALL SECTIONS, REMOVE THESE MATERIALS TO A CLEARLY CUT, STRAIGHT LINE, ACCURATELY ESTABLISHED.
- REMOVE FROM THE SITE AND DISPOSE OF LEGALLY. ALL EXISTING MATERIALS, DEMOLITION DEBRIS, TRASH, RUBBISH AND ITEMS THAT WILL NOT BE USED IN THE NEW WORK OR WILL NOT BE REUSED BY THE OWNER. STORAGE OF DEBRIS WILL NOT BE PERMITTED. ALL DEBRIS TO BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS.
- COORDINATE REMOVAL OF ANY RATED ASSEMBLIES WITH LOCAL OFFICIALS BEFORE COMMENCING WORK.

C. M.E.P. DEMOLITION NOTES

- SEE ELECTRICAL, HVAC, PLUMBING AND FIRE PROTECTION DRAWINGS FOR LOCATION OF NEW UTILITIES AND DEMOLITION OF EXISTING WORK NOT SHOWN ON THESE PLANS. GC TO COORDINATE ALL WORK WITH SUBCONTRACTORS.
- WHERE EXISTING ELECTRICAL DEVICES OCCUR IN PARTITIONS INDICATED TO BE REMOVED, THE WIRING SHALL BE REMOVED, ALL ELECTRICAL LINES BEING DISCONNECTED SHALL BE ADEQUATELY TRACED AND RECONNECTED AS REQUIRED TO ENSURE PROPER FUNCTION FOR THE ADJACENT AREAS AND TO ENSURE PROPER FUNCTION OF THE EXISTING BUILDING EQUIPMENT OR SYSTEM TO REMAIN. ELECTRICAL CONTRACTOR TO VERIFY ALL ELECTRICAL SYSTEMS PRIOR TO THE COMMENCEMENT OF WORK.
- WHERE EXISTING PLUMBING LINES ARE TO BE REWORKED OR REMOVED, ALL PLUMBING LINES BEING DISCONNECTED SHALL BE ADEQUATELY TRACED AND RECONNECTED AS REQUIRED TO ENSURE PROPER FUNCTION FOR THE ADJACENT AREAS AND TO ENSURE PROPER FUNCTION OF THE EXISTING BUILDING EQUIPMENT TO REMAIN IN PLACE.
- WHERE EXISTING HVAC LINES, DUCTWORK, ETC. ARE TO BE REWORKED, ALL LINES AND EQUIPMENT BEING DISCONNECTED SHOULD BE ADEQUATELY TRACED AND RECONNECTED AS REQUIRED TO ENSURE PROPER FUNCTION FOR THE ADJACENT AREAS AND TO ENSURE PROPER FUNCTION TO THE EXISTING BUILDING EQUIPMENT OR SYSTEMS TO REMAIN.
- COORDINATE WITH MECHANICAL AND ELECTRICAL DRAWINGS FOR LOCATIONS OF ALL NEW PENETRATIONS THRU ROOF, FLOORS, WALLS, AND CEILINGS.

D. CLEANING


- CONTRACTOR IS FULLY RESPONSIBLE FOR THE CLEANING AND PREPARING OF ALL FLOOR, WALL AND CEILING SURFACES FOR THE INSTALLATION OF NEW MATERIALS AS SCHEDULED, UTILITIES, HVAC AND ELECT. SYSTEMS EQUIPMENT, ETC. AFTER DEMO CLEAN-UP.

OTHER: REMINDERS/SPECIFIC TO INDIVIDUAL PROJECTS

- EXISTING LARGE FLOOR OPENINGS TO BE FILLED ARE INDICATED. SMALLER PIPE HOLES, ETC., TO BE FILLED ARE NOT INDICATED ON THE DRAWINGS. REFER TO DETAILS FOR REQUIREMENTS FOR FILLING SAID OPENINGS.
- ALL EXISTING COLUMNS TO REMAIN UNLESS NOTED.
- ALL EXPOSED UNUSED PIPING AND CONDUITS SHALL BE REMOVED BY THE GENERAL CONTRACTOR. SEE SPECIFICATIONS FOR CAPPING.


GENERAL CONSTRUCTION NOTES

- ALL WORK IS TO BE PERFORMED IN PROFESSIONAL AND WORKMANLIKE MANNER, IN ACCORDANCE WITH ALL APPLICABLE FEDERAL & STATE CODES, INCLUDING THE INTERNATIONAL BUILDING CODE (IBC), THESE INCLUDE, BUT ARE NOT LIMITED TO, THE INTERNATIONAL EXISTING BUILDING CODE (IEBC), MASS STATE BUILDING CODE, THE AMERICAN NATIONAL STANDARD (ANSI), THE INTERNATIONAL ENERGY CONSERVATION CODE (IECC), THE NATIONAL ELECTRIC CODE (NEC), THE INTERNATIONAL PLUMBING CODE (IPC), THE INTERNATIONAL MECHANICAL CODE (IMC), AND THE NATIONAL FIRE PROTECTION STANDARDS, AS WELL AS ALL LOCAL REGULATIONS GOVERNING THE PROJECT.
- CONTRACTOR TO VISIT SITE AND TO VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD, AND REPORT ALL DISCREPANCIES TO ARCHITECT, PRIOR TO PROCEEDING WITH WORK.
- ALL MATERIALS USED ON THIS PROJECT SHALL BE IN COMPLIANCE WITH THE APPLICABLE INTERNATIONAL BUILDING CODE.
- THE CONTRACTOR SHALL MAINTAIN COMPLETE AND UP-TO-DATE DRAWINGS AT THE JOB SITE, AND SHALL SUBMIT ACCURATE AS-BUILT DRAWINGS TO ARCHITECT AND OWNER AT END OF PROJECT.
- THE INTENTION OF THE CONTRACT DOCUMENTS IS TO INCLUDE ALL LABOR, MATERIALS, EQUIPMENT AND OTHER ITEMS NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK.
- BY EXECUTING THE CONTRACT, THE CONTRACTOR REPRESENTS THAT THEY HAVE VISITED THE SITE AND HAVE FAMILIARIZED THEMSELVES WITH THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED.
- THE ARCHITECT WILL HAVE AUTHORITY TO REJECT WORK WHICH DOES NOT CONFORM TO THE CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK, USING THEIR BEST SKILLS AND ATTENTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES, & SHORING, AND FOR COORDINATING THE WORK OF ALL SUB-CONTRACTORS.
- EACH CONTRACTOR SHALL PERFORM ALL REQUIRED CUTTING AND PATCHING FOR THEIR OWN TRADE, UNLESS OTHERWISE NOTED.
- DRAWINGS SHALL NOT BE SCALED TO OBTAIN DIMENSIONS.
- CONTRACTOR SHALL PROPERLY PROTECT AND MAKE SAFE WORK PREMISES.
- THE CONTRACTOR SHALL KEEP THE WORKSITE CLEAN AND TIDY, AND AT ALL TIMES SHALL KEEP THE PREMISES FREE FROM ACCUMULATION OF WASTE MATERIALS OR TRASH CAUSED BY THEIR OPERATIONS.
- ALL EXITS SHALL BE KEPT READILY ACCESSIBLE AND UNOBSTRUCTED AT ALL TIMES AND SHALL MAINTAIN REQUIRED EMERGENCY EGRESS DURING CONSTRUCTION.
- THE CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE OWNER AND THE ARCHITECT, AND THEIR AGENTS AND EMPLOYEES, FROM AND AGAINST ANY CLAIMS, DAMAGES, LOSSES AND EXPENSES INCLUDING ATTORNEY'S FEES ARISING OUT OF OR RESULTING FROM THE PERFORMANCE OF THE WORK.
- THE CONTRACTOR SHALL PAY ALL FEES AND SECURE PERMITS FROM ALL AGENCIES HAVING JURISDICTION AND AT COMPLETION SHALL SEE THAT THE PROJECT IS SIGNED OFF BY THE APPROPRIATE AUTHORITY HAVING JURISDICTION.
- WEATHER PROTECTION:** THE CONTRACTOR SHALL AT ALL TIMES PROVIDE PROTECTION AGAINST THE RAIN, WIND, STORM, FROST, OR HEAT SO AS TO MAINTAIN ALL WORK MATERIALS, APPARATUS, AND FIXTURES FROM INJURY OR DAMAGE.
- THE CONTRACTOR SHALL PROTECT ALL AREAS OUTSIDE THE CONTRACT LIMITS AND RESTORE ALL SUCH PROPERTY TO ITS CONDITION PRIOR TO THE START OF THE WORK.
- DAMAGE:** ALL WORK DAMAGED BY FAILURE TO PROVIDE PROTECTION SHALL BE REMOVED AND REPLACED WITH NEW WORK AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR SHALL UNCONDITIONALLY GUARANTEE ALL MATERIALS AND WORKMANSHIP UNTIL THE DATE OF OWNER'S ACCEPTANCE AND SHALL REPLACE ANY DEFECTIVE WORK WITHIN THAT PERIOD WITHOUT EXPENSES TO THE OWNER AND PAY FOR ALL DAMAGES TO OTHER PARTS OF THE BUILDING CAUSED BY REPAIR OF THEIR WORK.
- ALL FINISHES SHALL COMPLY WITH THE LIMITS FOR FIRE RESISTANCE/FLAMMABILITY AS SPECIFIED IN THE APPLICABLE INTERNATIONAL BUILDING CODE.
- ALL DEMOLITION AND RELOCATING OF EXISTING MEP SYSTEMS EFFECTING NEW PLUMBING, HVAC, AND ELECTRICAL SYSTEMS SHALL BE COORDINATED WITH RESPECTIVE SUBCONTRACTORS. RELOCATE/REWORK ALL ACTIVE MECHANICAL AND ELECTRICAL LINES WHERE REQUIRED DUE TO REMOVALS AND NEW LAYOUT. MODIFICATIONS FROM THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT BEFORE COMMENCING WORK.
- CONTRACTORS SHALL COORDINATE WITH PROPERTY MANAGER AS REQUIRED WHEN ITEMS OF NEW PLUMBING WORK REQUIRE ACCESS TO ADJACENT COMMON AREAS, AND TENANT SPACES OUTSIDE AREA OF WORK. REPLACE AND RESTORE FINISHES TO MATCH AFTER COMPLETION OF WORK.
- PROVIDE ALL BLOCKING REQUIRED TO INSTALL MILLWORK, EQUIPMENT, CASEWORK, GRAB BARS, RAILINGS, ETC. TYPE AND LOCATION SHALL BE SUBJECT TO REVIEW BY ARCHITECT.
- FOAM IN PLACE INSULATION FOR SMALL GAPS AND VOIDS.
- CAULK ALL JOINTS OF DISSIMILAR MATERIALS.
- PLAN DIMENSIONS ARE TO FACE OF PARTITION AT INTERIOR AND FACE OF FOUNDATION AT EXTERIOR, UNLESS OTHERWISE NOTED.
- REFER TO OWNERS ENVIRONMENTAL REPORT REGARDING CONTAMINANTS AND ASBESTOS ON THE PROJECT SITE/BUILDING.




A EXTERIOR WALL ASSEMBLY - 1 HOUR RATED
SCALE: 1" = 1'-0"

B EXTERIOR WALL ASSEMBLY @ FOUNDATION WALL
SCALE: 1" = 1'-0"




C1 INTERIOR WALL ASSEMBLY - 1 HOUR RATED
SCALE: 1" = 1'-0"

C2 INTERIOR WALL ASSEMBLY - 2 HOUR RATED
SCALE: 1" = 1'-0"



D1 INTERIOR WALL ASSEMBLY - 1 HOUR RATED
SCALE: 1" = 1'-0"

D2 INTERIOR WALL ASSEMBLY - 2 HOUR RATED
SCALE: 1" = 1'-0"



E TENANT SEPARATE ASSEMBLY - 1 HOUR RATED
SCALE: 1" = 1'-0"

2021 BUILDING ENVELOPE REQUIREMENTS WITH 225 CMR, CHAPTER 22.00;
CLIMATE ZONE 5
GROUP R BUILDING
WSF = 0.59
MAXIMUM HEERS RATING = 52
(1) 50A CIRCUIT PER DWELLING UNIT FOR AC LEVEL II CHARGER
ROOF TO BE SOLAR READY

ASHRAE 90.1 & STRETCH CODE = +15% BETTER INSULATION

FENESTRATION	U-FACTOR	U-0.26, SHGC=0.40
SKYLIGHT	U-FACTOR	U-0.47
CEILING	R-49	U-0.021
WOOD-FRAMED WALL	R-34.5	U-0.029
	OR R-23 + R-4 CI	
MASS WALL	R-20	U-0.071
FLOOR	R-34.5	U-0.028
BASEMENT WALL	R-22	U-0.043
	OR R-15+R-4 CI	
SLAB	R-12CI	FOR 4'-0"

ARCHITECT:

DIXON SALO ARCHITECTS INCORPORATED
FIRST FLOOR
300 MAIN STREET
WORCESTER, MASSACHUSETTS 01608
(508) 752-5333
(508) 752-5333
ADMIN@DIXONSALOARCHITECTS.COM

ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

<input type="checkbox"/>	SCHEMATIC	07.20.2023
<input type="checkbox"/>	DESIGN DEVELOPMENT	10.25.2023
<input type="checkbox"/>	BID	N/A
<input type="checkbox"/>	PERMIT	07.09.2024
<input type="checkbox"/>	CONSTRUCTION	
<input type="checkbox"/>	EXISTING CONDITIONS	

DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH
PROJECT TITLE:	5-UNIT RESIDENTIAL IN HISTORIC DISTRICT 114 AUSTIN ST WORCESTER, MA 01609
SHEET TITLE:	GENERAL NOTES & DETAILS

SHEET NUMBER:
T-1.1

ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
REVISION DATE	




DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 CONCEPTUAL FOUNDATION PLAN

SHEET NUMBER:

A-0.1



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

4

3

2

1

REVISION DATE

DATE: 07.09.2024

SCALE: AS NOTED

PROJECT: 2022.75



DRAWN: PL

CHECKED: JGH


PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 BASEMENT PLAN


SHEET NUMBER:
A-1.0



BASEMENT PLAN
 SCALE: 1/4" = 1'-0"



1
A-2.1









ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

	SCHEMATIC	07.20.2023
	DESIGN DEVELOPMENT	10.25.2023
	BID	N/A
	PERMIT	07.09.2024
	CONSTRUCTION	
	EXISTING CONDITIONS	

4	
3	
2	
1	
REVISION DATE	

DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 FIRST FLOOR PLAN

SHEET NUMBER:

FIRST FLOOR PLAN
 SCALE: 1/4" = 1'-0"







A-1.1

ARCHITECTS STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

	SCHEMATIC	07.20.2023
	DESIGN DEVELOPMENT	10.25.2023
	BID	N/A
	PERMIT	07.09.2024
	CONSTRUCTION	
	EXISTING CONDITIONS	

4	
3	
2	
1	
REVISION DATE	



DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609


SHEET TITLE:
 SECOND FLOOR PLAN

SHEET NUMBER:

A-1.2



SECOND FLOOR PLAN
 SCALE: 1/4" = 1'-0"



ARCHITECTS STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE


DATE: 07.09.2024
 SCALE: AS NOTED
 PROJECT: 2022.75
 DRAWN: PL
 CHECKED: JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 ROOF PLAN

SHEET NUMBER:

A-1.3



ROOF CONSTRUCTION
EAST COAST ALUMINUM METAL ROOFING
 EAVE TO PEAK TITANIUM HIGH TEMPERATURE ICE AND WATER SHIELD.
 COMAR VENT 3 SYNTHETIC BREATHABLE UNDERLAYMENT.
 ALUMINUM FLASHINGS, PLUMBING VENTS AND CHIMNEY COLLARS AS REQUIRED.
 PERMALOCK ALUMINUM SHINGLES INSTALL PER EAST COAST ALUMINUM METAL ROOFING REQUIREMENTS FOR WARRANTY AND WORKMANSHIP.

ROOF PLAN
 SCALE: 1/4" = 1'-0"
 A-1.3

- LIST OF MATERIALS**
- ROOFING MATERIALS:**
SHINGLE - EAST COAST METAL ROOFING ALUMINUM ROOF SHINGLE - CHARCOAL GRAY
- SIDING MATERIALS:**
CLAPBOARD SIDING - FIBER CEMENT LAP SIDING SIMILAR TO JAMES HARDIE STATEMENT COLLECTION
PLANK LAP SIDING (7' EXPOSURE), COLOR - ARCTIC WHITE
- GUARDS & HANDRAILS:**
HANDRAILS - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
- FENESTRATION:**
WINDOWS - MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE
DOORS - ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
GARAGE DOOR - OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8X7', GRAY/WHITE, 12 WINDOW ARCHED, CLEAR, BARCELONA HINGE, BARCELONA PULL
SHUTTER - MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X40' - SPANISH CEDAR, PAINT GRADE, FACTORY PRIMED WHITE, PAINTED BLACK
CORNER MOLDING - JAMES HARDIE HARDITRIM 1/2" TRIM - SMOOTH, PAINTED WHITE
DECOR - TREX TRANSCEND LINEAGE - JASPER
FENCING - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
FRAMEWORK - 408 VERANDA WHITE GARDEN VINYL LATTICE
COLUMN - BROSCO DS3 ALUMINUM COLUMN - RECESSED
BRACKET - BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2
MOLDING - BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901
- EXTERIOR LIGHTING FIXTURES:**
HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT
HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT
- RETAINING WALL:**
STONE STRONG 6-28SF CHISELED GRANITE TEXTURE BLOCKS W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	


4	
3	
2	
1	
	REVISION DATE

DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
114 AUSTIN ST
WORCESTER, MA 01609

SHEET TITLE:
SIDE ELEVATION

SHEET NUMBER:



SIDE ELEVATION
SCALE: 1/4" = 1'-0"

A-2.0

- LIST OF MATERIALS**
- ROOFING MATERIALS:**
SHINGLE - EAST COAST METAL ROOFING ALUMINUM ROOF SHINGLE - CHARCOAL GRAY
- SIDING MATERIALS:**
CLAPBOARD SIDING - FIBER CEMENT LAP SIDING SIMILAR TO JAMES HARDIE STATEMENT COLLECTION
PLANK LAP SIDING (7' EXPOSURE), COLOR - ARCTIC WHITE
- GUARDS & HANDRAILS:**
HANDRAILS - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
- FENESTRATION:**
WINDOWS - MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE
DOORS - ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
GARAGE DOOR - OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8X7', GRAY/WHITE, 12 WINDOW ARCHED, CLEAR
BARCELONA HINGE, BARCELONA PULL
SHUTTER - MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X40" - SPANISH CEDAR, PAINT GRADE, FACTORY PRIMED
WHITE, PAINTED BLACK
CORNER MOLDING - JAMES HARDIE HARDITRIM 1/2" TRIM - SMOOTH, PAINTED WHITE
DECOR - TREX TRANSCEND LINEAGE - JASPER
FENCING - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
FRAMEWORK - 408 VERANDA WHITE GARDEN VINYL LATTICE
COLUMN - BROSCO DS3 ALUMINUM COLUMN - RECESSED
BRACKET - BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2
MOLDING - BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901
- EXTERIOR LIGHTING FIXTURES:**
HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT
HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT
- RETAINING WALL:**
STONE STRONG 6-28SF CHISELED GRANITE TEXTURE BLOCKS W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE


DATE: 07.09.2024
SCALE: AS NOTED
PROJECT: 2022.75
DRAWN: PL
CHECKED: JGH

PROJECT TITLE:
5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
114 AUSTIN ST
WORCESTER, MA 01609

SHEET TITLE:
QUINCY STREET ELEVATION

SHEET NUMBER:

A-2.1



QUINCY STREET ELEVATION
SCALE: 1/4" = 1'-0"

11111 CLARK STREET
 SUITE 200
 WILMINGTON, MA 01890
 TEL: 508.725.5333
 FAX: 508.725.5333
 WWW.DIXONSALOARCHITECTS.COM

- LIST OF MATERIALS**
- ROOFING MATERIALS:**
SHINGLE - EAST COAST METAL ROOFING ALUMINUM ROOF SHINGLE - CHARCOAL GRAY
- SIDING MATERIALS:**
CLAPBOARD SIDING - FIBER CEMENT LAP SIDING SIMILAR TO JAMES HARDIE STATEMENT COLLECTION
PLANK LAP SIDING (7' EXPOSURE), COLOR - ARCTIC WHITE
- GUARDS & HANDRAILS:**
HANDRAILS - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
- FENESTRATION:**
WINDOWS - MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE
DOORS - ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
GARAGE DOOR - OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8X7', GRAY/WHITE, 12 WINDOW ARCHED, CLEAR, BARCELONA HINGE, BARCELONA PULL
SHUTTER - MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X40" - SPANISH CEDAR, PAINT GRADE, FACTORY PRIMED WHITE, PAINTED BLACK
CORNER MOLDING - JAMES HARDIE HARDITRIM 1/2" TRIM - SMOOTH, PAINTED WHITE
DECOR - TREX TRANSCEND LINEAGE - JASPER
FENCING - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
FRAMEWORK - 408 VERANDA WHITE GARDEN VINYL LATTICE
COLUMN - BROSCO DS9 ALUMINUM COLUMN - RECESSED
BRACKET - BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2
MOLDING - BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901
- EXTERIOR LIGHTING FIXTURES:**
HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT
HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT
- RETAINING WALL:**
STONE STRONG 6-28SF CHISELED GRANITE TEXTURE BLOCKS W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE


DATE: 07.09.2024
 SCALE: AS NOTED
 PROJECT: 2022.75
 DRAWN: PL
 CHECKED: JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 AUSTIN STREET ELEVATION

SHEET NUMBER:

A-2.2



AUSTIN STREET ELEVATION
 SCALE: 1/4" = 1'-0" R2.2

LIST OF MATERIALS

ROOFING MATERIALS:
SHINGLE - EAST COAST METAL ROOFING ALUMINUM ROOF SHINGLE - CHARCOAL GRAY

SIDING MATERIALS:
CLAPBOARD SIDING - FIBER CEMENT LAP SIDING SIMILAR TO JAMES HARDIE STATEMENT COLLECTION
PLANK LAP SIDING (7' EXPOSURE), COLOR - ARCTIC WHITE

GUARDS & HANDRAILS:
HANDRAILS - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS

FENESTRATION:
WINDOWS - MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE
DOORS - ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
GARAGE DOOR - OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8X7', GRAY/WHITE, 12 WINDOW ARCHED, CLEAR, BARCELONA HINGE, BARCELONA PULL
SHUTTER - MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X46" - SPANISH CEDAR, PAINT GRADE, FACTORY PRIMED WHITE, PAINTED BLACK
CORNER MOLDING - JAMES HARDIE HARDITRIM 1/2" TRIM - SMOOTH, PAINTED WHITE
DECORATIVE - TREX TRANSCEND LINEAGE - JASPER
FENCING - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALUSTERS
FRAMEWORK - 408 VERANDA WHITE GARDEN VINYL LATTICE
COLUMN - BROSCO DS3 ALUMINUM COLUMN - RECESSED
BRACKET - BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2
MOLDING - BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901

EXTERIOR LIGHTING FIXTURES:
HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT
HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT

RETAINING WALL:
STONE STRONG 6-28SF CHISELED GRANITE TEXTURE BLOCKS W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE

DATE: 07.09.2024
SCALE: AS NOTED
PROJECT: 2022.75
DRAWN: PL
CHECKED: JGH

PROJECT TITLE:
5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
114 AUSTIN ST
WORCESTER, MA 01609



SHEET TITLE:
REAR ELEVATION

SHEET NUMBER:

A-2.3



REAR ELEVATION
SCALE: 1/4" = 1'-0"



MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE

ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
DOOR = 3'-0" x 6'-8" WITH (2) 3/4" SIDELITES
NO SIDELITES @ CARRIAGE HOUSE ENTRY DOOR

MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X48" - SPANISH CEDAR,
FRONT DOOR WINDOWS, PAINT GRADE, FACTORY PRIMED WHITE, PAINTED BLACK

JAMES HARDIE 8" WIDE HARDIETRIM 3/4" TRIM - SMOOTH, PAINTED WHITE

LIST OF MATERIALS
ROOFING MATERIALS:
 SHINGLE - EAST COAST METAL ROOFING ALUMINUM ROOF SHINGLE - CHARCOAL GRAY

SIDING MATERIALS:
 CLAPBOARD SIDING - FBER CEMENT LAF SIDING SIMILAR TO JAMES HARDIE STATEMENT COLLECTION
 PLANK LAF SIDING (7" EXPOSURE), COLOR - ARCTIC WHITE

GUARDS & HANDRAILS:
 HANDRAILS - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALLUSTERS

FENESTRATION:
 WINDOWS - MARVIN SIGNATURE SERIES, ULTIMATE WOOD, PAINTED WHITE
 DOORS - ANDERSEN WOOD ENTRY DOOR - PAINTED WHITE
 GARAGE DOOR - OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8'X7', GRAY/WHITE, 12 WINDOW ARCHED, CLEAR, BARCELONA HINGE, BARCELONA PULL
 SHUTTER - MILLWORK TRADERS STANDARD DUTY FIXED LOUVER 15'X48" - SPANISH CEDAR, PAINT GRADE, FACTORY PRIMED WHITE, PAINTED BLACK
 CORNER MOLDING - JAMES HARDIE HARDIETRIM 1/2" TRIM - SMOOTH, PAINTED WHITE
 DECKING - TREX TRANSCEND LINEAGE - JASPER
 FENCING - VERANDA 36 IN. TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL BALLUSTERS
 FRAMEWORK - 4x8 VERANDA WHITE GARDEN VINYL LATTICE
 COLUMN - BROSCO DSI ALUMINUM COLUMN - RECESSED
 BRACKET - BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2
 MOLDING - BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901

EXTERIOR LIGHTING FIXTURES:
 HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT
 HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT

RETAINING WALL:
 STONE STRONG 6-28SF CHISELED GRANITE TEXTURE BLOCKS W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

<input type="checkbox"/>	SCHEMATIC	07.20.2023
<input type="checkbox"/>	DESIGN DEVELOPMENT	10.25.2023
<input type="checkbox"/>	BID	N/A
<input type="checkbox"/>	PERMIT	07.09.2024
<input type="checkbox"/>	CONSTRUCTION	
<input type="checkbox"/>	EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE




DATE: 07.09.2024
 SCALE: AS NOTED
 PROJECT: 2022.75
 DRAWN: PL
 CHECKED: JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
PROPOSED MATERIALS PHOTOS

SHEET NUMBER:

A-2.4



4x8 VERANDA WHITE GARDEN VINYL LATTICE

EAST COAST METAL ROOFING ALUMINUM SMOOTH CHARCOAL GRAY
5' x 12' EXPOSURE

OVERHEAD DOOR COMPANY MODEL 303 ARCHED - 8'X7', GRAY/WHITE, 12
WINDOW ARCHED, CLEAR, BARCELONA HINGE, BARCELONA PULL

LIGHTING FIXTURE - HINKLEY FORGE 16-1/2" HIGH BLACK OUTDOOR BARN WALL LIGHT




JAMES HARDIE FIBER CEMENT SIDING - ARCTIC WHITE

VERANDA 42" TRADITIONAL WHITE POLY-COMPOSITE RAIL GATE KIT W/ METAL
BALLUSTERS

TREX TRANSCEND LINEAGE - JASPER, 6" x 3/4" BOARDS, PORCH DECK & TREADS

LIGHTING FIXTURE - HINKLEY FORGE 12" HIGH BLACK OUTDOOR WALL LIGHT




BROSCO DSI ALUMINUM COLUMN - RECESSED, PAINTED
9/3/2024 12:32 PM

BROSCO PVC OUTDOOR PRODUCTS BRACKETS - HBKT-2, PAINTED

BROSCO INTEX MILLED & PRIMED PVC MOLDING - 7901, PAINTED

RETAINING WALL - STONE STRONG 6-28 SF CHISELED GRANITE TEXTURE W/CAP



ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

REVISION DATE
4
3
2
1


DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609


SHEET TITLE:
 CARRIAGE HOUSE SECTION

SHEET NUMBER:


A-2.5




KITCHEN ELEVATION 'A'




KITCHEN ELEVATION 'B'




ELEVATION 'A'




ELEVATION 'B'




ELEVATION 'C'




ELEVATION 'D'




ELEVATION 'E'




ELEVATION 'F'



ELEVATION 'G'



ELEVATION 'G'



ELEVATION 'H'



ARCHITECT'S STAMP:

ENGINEER'S STAMP:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

4	
3	
2	
1	
	REVISION DATE

DATE:	07.09.2024
SCALE:	AS NOTED
PROJECT:	2022.75
DRAWN:	PL
CHECKED:	JGH

PROJECT TITLE:
5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
114 AUSTIN ST
WORCESTER, MA 01609


SHEET TITLE:
KITCHEN AND BATHROOM
INTERIOR ELEVATIONS

SHEET NUMBER:

A-6.0

DOOR SCHEDULE

DOOR NUMBER	DOOR				FRAME			HARDWARE													LOCATION	REMARKS							
	DOOR TYPE	DOOR MATERIAL	DOOR FINISH	LABEL	SIZE	FRAME TYPE	FRAME MATERIAL	FRAME FINISH	DETAILS	CONT HINGES	HINGES	LATCH SET	LOCKSET	LOCK	THRESHOLD	CLOSER	TIME-OUT MAGNETIC LOCK	PUSH / PULL	WEARSTRIPPING & SWEEP	KICK PLATE (PAIR RESCOVER)			GARAGE DOOR OPENER	MAGNETIC HOLD-OPEN	OFFSET HINGES (180° OPEN)	ELEC STRIKE	CARD READER	OVERHEAD DOOR OPENER	BIFOLD DOOR SET
BASEMENT																													
001	1	WD	-	-	3'-0"	7'-0"	F1	WD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
002	2	WD	PTD	-	8'-0"	7'-0"	F2	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
003	3	WD	PTD	C-LABEL	2'-10"	6'-8"	1-3/8"	F3	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
104	4	WD	PTD	-	3'-0"	6'-0"	1-3/4"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
104A	4A	WD	PTD	-	3'-0"	6'-0"	1-3/4"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
105	5	WD	PTD	C-LABEL	2'-8"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
106	5	WD	PTD	C-LABEL	2'-8"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
107	7	WD	PTD	-	6'-0"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
108	5	WD	PTD	-	3'-0"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
205	3	WD	PTD	-	2'-10"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
206	6	WD	PTD	-	2'-6"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
208	7	WD	PTD	-	6'-0"	6'-8"	1-3/8"	F4	WD	PTD	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



DOOR ELEVATIONS 1/4" = 1'-0"

ROOM FINISH SCHEDULE

AREA	FLOOR	BASE	WALLS	CEILING	REMARKS
	LUXURY VINYL TILE	CARPET	12" X 12" CERAMIC TILE	SEALED CONCRETE	WOOD TREADS AND RISERS
		4" VINYL COVE	4" WOOD BASE	3" X 6" CERAMIC COVE	NONE
			GWB PAINTED	GWB PAINTED & SANDED	WET WALL - FULL HEIGHT CERAMIC TILE. SUBWAY TILE
				GWB PAINTED	GWB PAINTED & SANDED
GARAGE					
MECH/ELEC					
SPRINKLER					
BASEMENT STAIRS					
LIVING ROOM					
KITCHEN/DINING					
CORRIDORS					
HALF BATHROOM					
1ST-2ND FLOOR STAIRS					
BEDROOM 2					
BEDROOM 1					
BATHS					

WINDOW SCHEDULE

TYPE	MATERIAL	MANUFACTURER	MODEL NUMBER	ROUGH OPENING			REMARKS
				WIDTH	HEIGHT	HEAD RO. AFF.	
A	WD	MARVIN	3454	3'-4"	5'-4"	6'-8" +/-	1/2 DH LITES, EGRESS
B	WD	MARVIN	3450	3'-4"	5'-0"	6'-8" +/-	1/2 DH LITES, EGRESS
C	WD	MARVIN	3440	3'-4"	4'-0"	6'-8" +/-	1/2 DH LITES
D	WD	MARVIN	3438	3'-4"	3'-8"	6'-8" +/-	1/2 DH LITES
E	WD	MARVIN	3434	3'-4"	3'-4"	6'-8" +/-	1/2 DH LITES
F	WD	MARVIN	2850	3'-4"	5'-4"	6'-8" +/-	3x4 DIVIDED LITES
G	WD	MARVIN	2844	3'-4"	4'-0"	6'-8" +/-	3 x 3 DIVIDED LITES

ARCHITECT:

DIXON SALO ARCHITECTS
 INCORPORATED
 300 MAIN STREET, SUITE 300
 WORCESTER, MA 01609
 (508) 755-0333 (F) 508-752-5348
 ADMIN@DIXONSALOARCHITECTS.COM

ARCHITECT'S STAMP:

ENGINEER:

ENGINEER'S STAMP:

GENERAL INFORMATION:

SCHEMATIC	07.20.2023
DESIGN DEVELOPMENT	10.25.2023
BID	N/A
PERMIT	07.09.2024
CONSTRUCTION	
EXISTING CONDITIONS	

NO.	REVISION DATE
4	
3	
2	
1	

DATE: 07.09.2024
 SCALE: AS NOTED
 PROJECT: 2022.75
 DRAWN: PL
 CHECKED: JGH

PROJECT TITLE:
 5-UNIT RESIDENTIAL IN HISTORIC DISTRICT
 114 AUSTIN ST
 WORCESTER, MA 01609

SHEET TITLE:
 DOOR AND WINDOW TYPES,
 FINISH SCHEDULE

SHEET NUMBER:
A-8.0